

6<sup>th</sup> of October 2021

# Intermediate Results from the Research Project SeeOff

Prof. Dr. Silke Eckardt, Vanessa Spielmann, Mandy G. Ebojie  
City University of Applied Sciences Bremen, Germany



# SeeOff

*Strategieentwicklung zum effizienten  
Rückbau von Offshore-Windparks*

*Development of efficient strategies for  
offshore wind farm decommissioning*

Supported by:



Federal Ministry  
for Economic Affairs  
and Energy

on the basis of a decision  
by the German Bundestag

- About our project
- The reference offshore windfarm
- Considered decommissioning scenarios
- Preview of intermediate results
  - campaign durations and high-level campaign plan
  - GHG emissions
  - Recycling rate
- Summary and Outlook




# The Project SeeOff

# SeeOff

Development of  
efficient strategies for  
offshore wind farm  
decommissioning

- **Project duration:**  
3.5 years (November 1<sup>st</sup> 2018 – April 31<sup>st</sup> 2022)
- **Project coordination:** Prof. Dr.-Ing. Silke Eckardt  
City University of Applied Sciences Bremen
- **Project objectives:** Development and assessment  
of efficient **Decommissioning Strategies**
- **Strategies shall**
  - comply with **legal requirements**,
  - be **cost efficient**,
  - ensure **safety at work**,
  - ensure **environmental protection**, low **GHG emissions** and **resource efficiency**
  - be **publicly accepted**.



Supported by:



on the basis of a decision  
by the German Bundestag

<b>Turbine (WTG):</b>	<b>80 x SWT 3.6 120</b>
<b>Foundation (FOU):</b>	<b>Transition Piece (TP) with grouted connection to Monopile (MP)</b> MP: 680 t, length 65 m, diameter max. 6m, wall thickness max. 126 mm; TP: 250 t, length of 27 m
<b>Water Depth:</b>	<b>between 20m and 30m</b>
<b>Inter Array Cable (IAC):</b>	<b>33kV (length approx. 100 km)</b>
<b>Scour Protection:</b>	<b>2 layer (Filter: 20 – 200 mm, Armour: 350 – 550 mm)</b>
<b>Offshore Substation: (OSS)</b>	<b>Weight approx. 3,000 t Jacket foundation, approx. 850 t</b>
<b>Harbour:</b>	<b>Bremerhaven (for a better comparability just one harbor assumed)</b>




"Windpark DanTysk / DanTysk wind farm" by Vattenfall is licensed under [CC BY-NC-ND 2.0](#)

**System Boundary:** 1. Reference offshore wind farm, incl. AC export cable connection to converter,  
2. From dismantling/ decommissioning (offshore) to secondary raw material (onshore)


## 1 Offshore Dismantling/Decommissioning

Area of responsibility: OWF




## 2 Waste Management Onshore

### 2.1 Dismantling and preparation at the harbour



[...]

### 2.2 Processing and disposal




[...]

Sekundärrohstoff

## Wind Turbine Generator (WTG)


	Base Scenario WTG	Alternative Scenarios WTG
Concept	„Reverse Installation“ Dismantling in reverse installation order, interface is tower/TP flange	./.
Logistics	Jack-Up Vessel (JUV (WTG)) for both dismantling and transport	JUV (WTG) for dismantling; feeder vessel for transport (Deck Carrier) <b>(S1)</b>



"Brave Tern Berthed @ Esbjerg-Denmark 03-07-2019"  
by Rab , is licensed under CC BY 2.0


## WTG-Foundation (WTG-FOU)

	Base Scenario WTG FOU	Alternative Scenarios WTG-FOU
Concept	<p><b>2 cuts:</b> First cut: internal cut below TP, Abrasive water jetting technology (AWJ) Second cut: MP internal cut, min. 1 m below seabed, AWJ technology,</p>	<p><b>2 cuts:</b> First cut: internal cut below TP, AWJ technology Second cut: MP internal cut, 3-5m above seabed, AWJ technology, <b>Alternative</b> Second cut with diamond wire cutting machine (DWCM)</p> <p><b>One cut + Vibratory extraction (S8):</b> cut below TP with AWJ; complete retrieval of MP by vibratory extraction</p>
Logistics	Shuttle concept with JUV (WTG-FOU)	JUV (WTG-FOU) for dismantling, feeder vessel for transport (Deck Carrier) <b>(S2+3)</b>



## Scour Protection


	Base Scenario Scour Protection	Alternative Scenarios Scour protection
Concept	Removal of stones with cable dredger	No removal of scour protection
Logistics	Multipurpose vessel with cable dredger (Cargo Barge for transport)	./.





## Inner Array Cable (IAC)

	Base Scenario IAC	Alternative Scenarios IAC
Concept	Complete removal of all cables	Removal of cables around FOU, burial of cable end and no removal of buried cables
Logistics	Walk to work (W2W) Vessel and Cable Lay Vessel	W2W Vessel and JUV (cable, support)



(Quelle: <https://www.tennet.eu/news/detail/tennet-develops-innovative-submarine-cable-with-suppliers/>)

## Selection

1. Campaign Planning -> to estimate decommissioning project duration and duration of single campaigns as well as for cost simulation
2. Green House Gas (GHG) Emissions -> CO<sub>2</sub>-Equivalents
3. Resource Efficiency -> Recovery Rate

### Scenarios considered:

- Base scenario: WTG dismantling with JUV and „reverse installation“; Logistics: shuttle transport with JUV
- Scenario 3: dismantling as Base scenario; Logistics: Feeder concept with feeder vessels
- Scenario 8: complete removal of monopile foundation with vibratory extraction; logistics as base case

## Assumptions

- Number of simultaneous processes at site (decom of WTG, IAC, FOU) are not limited
- Consideration of weather risks by means of safety factors on process durations depending on process activity type
- Consideration of process risks by using range in process activity durations





Process	Duration p.unit	Duration total	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
Dismantling WTG	0,9-1,7 d	14 w (11-20)		10		20		30	40		50		60		70	80								
Removal of IAC	0,6-0,9 d	8,6 w (7-10)								22		44		66		86								
Removal of export cables	3-4 d	1 w (0,8-1,1)																						
Dismantling Foundation	2,7-5,3 d	45 w (31-61)											2	4	6	8	10	12	14	16	18			
Dismantling OSS	7,5-12 d	1,4 w (1,1-1,7)																						
Removal of Scour protection	0,5-0,6 d	6 w (5,3-6,5)																						
Σ Weight landing at port in tmax			800 t/ 3,5 days										1220 t / 8 days											

Process	Duration p.unit	Duration total	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21							
Dismantling WTG	1,1-1,5 d	14,5 w (12-16)															8	16	24	32	40	48	56	64	72	80				
Removal of IAC	0,6-0,9 d	8,6 w (7-10)								22										44	66			86						
Removal of export cables	3-4 d	1 w (0,8-1,1)																												
Dismantling Foundation	2,3-5,7 d	46 w (26-65)											4												8	12	16	20		
Dismantling OSS	7,5-12 d	1,4 w (1,1-1,7)																												
Removal of Scour protection	0,5-0,6 d	6 w (5,3-6,5)																												

$\Sigma$ Weight landing at port in tmax	3200 t /10 days	3500 t/16 days
---	-----------------	----------------

## Conclusion

- Similar overall project duration (process durations of the individual campaigns varies only slightly): approx. 60 to 70 weeks
- But: higher uncertainty regarding process durations for removal of monopile foundation with vibratory extraction
- Only small time reduction with feeder concept due to relatively short distance to shore (110nm)
- The process sequence must be coordinated with the dismantling capacities (cranes, storage areas, dismantling resources, etc.) at the port

## Calculation of CO<sub>2</sub>-Equivalents of the vessels

based on

- Vessel fuel consumption (at transit, operation, standby)
- Fuel type (Marine Gas Oil, Heavy Fuel Oil)
- Duration of the fuel consumption

Conversion factors for MGO and HFO derive from UK Government Conversion Factors for greenhouse gas (GHG) reporting (2021)

Global warming potential (GWP<sub>100</sub>) of the Intergovernmental Panel on Climate Change (IPCC) were applied to calculate CO<sub>2</sub>-Equivalentents (Stocker et al. 2013)

Pollutant	GWP <sub>100</sub> in kg CO <sub>2</sub> -eq/kg
CO <sub>2</sub>	1
CH <sub>4</sub>	28
N <sub>2</sub> O	265



## Mean CO<sub>2</sub>-Equivalents of the vessels

Baseline scenario:

113 857 t CO<sub>2</sub>-Equivalents

Scenario 3 (Feeder concept):

172 290 t CO<sub>2</sub>-Equivalents

Vessel	Baseline scenario	S3: feeder concept
JUV (WTG)	28 333 t	9 776 t
JUV (WTG-FOU)	57 045 t	4 2878 t
Deck Carrier	---	91 127 t



## Calculation of recovery rate based on recovery rate of construction and demolition waste (2011/753/EU):


Recovery rate of construction and demolition waste, in % =


$$\frac{\text{Materially recovered amount of construction and demolition waste}}{\text{Total amount of generated construction and demolition waste}}$$

- Only construction and demolition waste brought ashore is considered
- Assumption: all materials and components are disposed
  - no reuse

## Mass balance of reference offshore wind farm

Overall mass: 228 171 t







## Summary and Outlook

- Durations vary only slightly between scenarios
  - Vessel concept (shuttle vs. feeder concept) influences GHG emissions
  - Complete removal of MP has only minor impact on overall recovery rate, but influences the amount of overall materials that will be recovered
- 
- Remaining indicators for costs, biodiversity and safety at work will be calculated
  - Indicators will be calculated for all scenarios
  - Results of individual indicator calculation are assessed in a multicriteria decision analysis
    - **Sustainable offshore wind farm decommissioning scenarios**

.... more Information on our website [www.seeoff.de](http://www.seeoff.de)

## 1. Workshop and Conferences

- Workshop: Decommissioning of Offshore Wind Farms: Requirements, Objectives and Challenges, September 19<sup>th</sup> 2019
- Expert-Workshop: Scope of Offshore Wind Farm Decommissioning – Impacts on the marine environment, April 23<sup>rd</sup> 2021
- SeeOff Conference on Technologies for Offshore Wind Decommissioning, June 10<sup>th</sup> 2021

## 2. Presentations and Paper

- Zukunft Offshore Konferenz des Bundesverbands der Windparkbetreiber Offshore e.V. (BWO), April 3<sup>rd</sup> 2020, Berlin
- Offshore Decommissioning Congress, September 16<sup>th</sup> 2020
- End of Life Issues and Strategies Seminar, WindEurope, November 18<sup>th</sup> -20<sup>th</sup> 2020
- International Conference on The Decommissioning of Offshore & Subsea Structures DECOM 2020, December 07<sup>th</sup> - 08<sup>th</sup> 2020
- Wind Energy Science Conference, May 25<sup>th</sup> – 28<sup>th</sup> 2021
- Spielmann et al., 2021. Integration of sustainability, stakeholder and process approaches for sustainable offshore wind farm decommissioning. Renewable and Sustainable Energy Reviews, 147.

# Thank you very much for your attention

**Prof. Dr.-Ing. Silke Eckardt**

Hochschule Bremen

Neustadtswall 30

28199 Bremen

+49 421 5905 3427

[silke.eckardt@hs-bremen.de](mailto:silke.eckardt@hs-bremen.de)

**Vanessa Spielmann**

Hochschule Bremen

Neustadtswall 30

28199 Bremen

+49 421 5905 2394

[Vanessa.spielmann@hs-bremen.de](mailto:Vanessa.spielmann@hs-bremen.de)

**Mandy G Ebojie**

Hochschule Bremen

Neustadtswall 30

28199 Bremen

+49 421 5905 2397

[mandy.ebojie@hs-bremen.de](mailto:mandy.ebojie@hs-bremen.de)



## References

- Stocker, T. F.; Qin, D.; Plattner, G.-K.; Tignor, M.; Allen, S. K.; Boschung, J. et al. (Hg.) (2013): Climate change 2013. The physical science basis Working Group I contribution to the Fifth assessment report of the Intergovernmental Panel on Climate Change. International Panel on Climate Change (IPCC). Cambridge, United Kingdom, New York, NY, USA: Cambridge University Press.
- UK Government Department for Business, Energy & Industrial Strategy (Hg.) (2021): UK Government GHG Conversion Factors for Company Reporting. conversion factors 2021: advanced set (for advanced users). <https://www.gov.uk/government/publications/greenhouse-gas-reporting-conversion-factors-2021> [Zugriff: 2021/08/24].